

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 32
7.00	Gulch, course N.W.
20.00	Set a basalt stone, 10x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
25.00	Trail, course S.E.
40.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for ¼ sec. corner marked ¼ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it.
51.00	Trail, course S.E.
60.00	Set a basalt stone, 16x9x6 ins., 12 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., raised a mound of earth 1½ ft. high, 3½ ft. base over it.
80.00	To the ¼ sec. corner between secs. 31 and 32. Land, rolling. E. ½. Land, level. W. ½. Soil, 1st rate. E. ½. Soil, 2nd rate. W. ½. Grass good on hill.
	From the 1/16 sec. corner, 20 chs. N. of ¼ sec. corner between secs. 31 and 32.
	I run
	East on random line through N. ½ of sec. 32.
	Var. 20° East.
	Setting temporary corners at every 20, 40 and 60 chains, and at
80.00	Intersect the N. and S. line, 20 lks. N. of 1/16 sec. corner between secs. 32 and 33.
	Thence I run
	N.89°51'W. on true line through N. ½ of sec. 32.
	Var. 20° E.
	Descend on plains.