

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 33
79.80	Intersect the N. and S. line, 35 lks. N. of 1/16 sec. cor. bet. secs. 32 and 33.
	Thence I run S.89°45'E. on true line through N. $\frac{1}{2}$ of sec. 33 Var. 21°30'E.
19.95	Set a basalt stone, 16x8x7 ins., 12 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
24.00	Top of hill.
39.90	Set basalt stone, 12x8x5 ins., 8 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
46.50	Road in pass, course N.W.
59.85	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
76.00	Summit.
79.80	To the 1/16 sec. corner between secs. 32 and 33. Land, level and mountainous. Soil, 1st rate. Good grass. June 22, 1889.

General Description

The part of this Township allotted is level or gently rolling, well adapted to farming. Good bunch grass.
No timber.