

Subdivisions of T. 1 N., R. 33 E.

Chains

Land, gently rolling or sloping toward North.
Soil, 1st rate.
Well adapted to agriculture.

East on random between secs. 2 and 11.

Var. $19\frac{1}{2}^{\circ}$ East.

Set temporary $\frac{1}{4}$ and $1/16$ sec. cors. at 20, 40 and 60
chains and at

79.85 Intersect N. and S. line, 25 lks. N. of cor. to secs. 1,
2, 11 and 12. Thence

N. $89^{\circ}49'W.$ on true line, between secs. 2 and 11.

Var. 20° East.

Descend.

19.96 Set basalt stone, 9x8x7 ins., 6 ins. in the ground for
 $1/16$ sec. cor. marked $1/16$ on N. face, raised mound
of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. Pits
impracticable.

21.50 Gulch, N.W. -300

39.92 Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for $\frac{1}{4}$
sec. cor. marked $\frac{1}{4}$ on North face. Dug pits, 18x18x12
ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., raised mound of
earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.

59.88 Deposited charred stake, 12 ins. in the ground for $1/16$
sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake,
 $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft.
base over it and in E. pit drove stake 2 ft. long,
2 ins. square, 12 ins. in the ground marked $1/16$ on N.
face.

60.50 Gulch, N.W. -20

79.85 Cor. to secs. 2, 3, 10 and 11.

Land, rolling.

Soil, 1st rate. Good grass.

North on random between secs. 2 and 3.

Var. $19\frac{1}{2}^{\circ}$ East.