

## Subdivisions of T. 1 N., R. 33 E.

Chains	Set temporary $\frac{1}{4}$ and $1/16$ sec. cors at 20, 40 and 60 chains and at	
78.40	Intersect N. bdy. Township, 60 lks. E. of cor. to secs. 2, 3, 34 and 35. Thence S. 26'E. on true line between secs. 2 and 3. Var. 21° East.	
18.40	Deposited charred stake, 12 ins. in the ground, for $1/16$ sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $1/16$ S. on W. face.	
38.40	Set basalt stone, 9x8x7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
48.30	Dry ditch, N.W.	
48.50	Wagon road, N.W.	
58.40	Deposited charred stake, 12 ins. in the ground, for $1/16$ sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins., square, 12 ins. in the ground marked $1/16$ S. on W. face.	
60.00	Dry ditch, W.	
78.40	Cor. to secs. 2, 3, 10 and 11. Land, mostly level. Soil, 1st rate. Well adapted to agriculture. Very little grass.	
	From cor. to secs. 33 and 34 on S. bdy. of Tp. I run North between secs. 33 and 34. Var. 20° East.	
4.00	Gulch, W.	-75
15.00	Summit hill, W.	+125
27.50	Gulch, S.W.	-80