

## Subdivisions of T. 1 N., R. 33 E.

Chains	North between secs. 21 and 22.	
	Var. 20° East.	
22.50	Canyon, W.	-400
40.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
60.00	Summit ridge, W.	+50
74.00	Dry gulch, W.	-50
80.00	Set basalt stone, 9x8x8 ins., 6 ins. in the ground, for cor. to secs. 15, 16, 21 and 22 marked with 3 notches on S. and E. edges. Dug pits, 18x18x12 ins., in each sec. $5\frac{1}{2}$ ft. dist., raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.	
	Land, rolling.	
	Soil, 2nd rate. Bunch grass.	
	East on random between secs. 15 and 22.	
	Var. 20° East.	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
79.65	Intersect E. bdy, 50 lks. N. of cor. to secs. 14, 15, 22 and 23. Thence	
	N.89°39'W. on true line between secs. 15 and 22.	
	Var. 22° East.	
39.82	Deposited charred stake, 12 ins. in the ground, for $\frac{1}{4}$ sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{4}$ S on N. face.	
	Descend gradual slope.	
79.65	Cor. to secs. 15, 16, 21 and 22.	
	Land, rolling.	
	Soil, 1st rate. Good grass.	
	North between secs. 15 and 16.	
	Var. 20° East.	