

Subdivisions of T. 1 N., R. 33 E.

Chains 40.00	Deposited charred stake, 12 ins. in the ground, for $\frac{1}{4}$ sec. cor. Dug pits, 18x18x12 ins., N. and S. of cor. $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on W. face.
80.00	Set basalt stone, 10x10x10 ins., 6 ins. in the ground, marked with 4 notches on S. and 3 notches on E. edges, for cor. to secs. 9, 10, 15 and 16. Dug pits, 18x18x12 ins., in each sec. $5\frac{1}{2}$ ft. dist. Raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it. Land, level. Soil, 1st rate. Fine grass. Well adapted to agriculture.
	East on random between secs. 10 and 15. Var. 20° East. Set temporary $\frac{1}{4}$ and 1/16 sec. cors. at 20, 40 and 60 chains, and at
79.53	Intersect N. and S. line, 39 lks. N. of cor. to secs. 10, 11, 14 and 15. Thence N. 89°43' West on true line between secs. 10 and 15. Var. 22° East.
3.80	Dry branch, N.
19.88	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
39.77	Set basalt stone, 12x12x12 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. and marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
59.65	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins.