

Subdivisions of T. 1 N., R. 33 E.

Chains 79.40	Intersect N. and S. line, 50 lks. N. of cor. to secs. 2, 3, 10 and 11. Thence N.89°39' West on true line between secs. 3 and 10. Var. 19½° E.
.40	Dry branch, N.W.
14.40	Wagon road, N.E.
19.85	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
39.70	Set basalt stone, 12x8x8 ins., 8 ins. in the ground, for ¼ sec. cor. marked ¼ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist. and raised mound of earth 1½ ft. high, 3½ ft. base over it.
59.50	Dry ditch, N.W..
59.55	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake, 2 ft. long, 2 ins. square 12 ins. in the ground, marked 1/16 S on N. face.
79.40	Cor. to secs. 3, 4, 9 and 10. Land, level. Soil, good. Bunch grass.
	North on random between secs. 3 and 4. Var. 21° East. Set temp. ¼ and 1/16 sec. cors. at 20, 40 and 60 chains and at
77.60	Intersect N. bdy. Township, 122 lks. E. of cor. to secs. 3, 4, 33 and 34. Thence S.52° E. on true line between secs. 3 and 4. Var. 21° East.
17.60	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake,