

Subdivisions of T. 1 N., R. 33 E.

Chains	<p>$5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $1/16$ S on W. face.</p>	
18.00	Wagon road, W.	
37.60	<p>Deposited charred stake, 12 ins. in the ground, for $\frac{1}{4}$ sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on W. face.</p>	
55.60	Draw or gulch, W.	-20
57.60	<p>Deposited charred stake, 12 ins. in the ground, for $1/16$ sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $1/16$ S on W. face.</p>	
77.60	<p>Cor. to secs. 3, 4, 9 and 10. Land, level. Soil, 1st rate. Some grass and weeds. Good farming land. August 2, 1887.</p>	
	<p>From cor. to secs. 32 and 33 on S. bdy. of Tp. I run North between secs. 32 and 33. Var. $21\frac{1}{8}$ E.</p>	
10.00	<p>Top of hill, E. and W. Descend.</p>	+500
40.00	<p>Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for $\frac{1}{2}$ sec. cor., marked $\frac{1}{2}$ on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p>	
48.75	Gulch, N.W.	-100
74.00	Trail bears N.E.	
80.00	<p>Set basalt stone, 12x8x6 ins., 8 ins. in the ground, for cor. to secs. 28, 29, 32 and 33 marked with 1 notch on</p>	