

## Subdivisions of T. 1 N., R. 33 E.

| Chains   |  |   |
|--|--|---|
|  | <p>S. and 4 notches on E. edges. Dug pits, 18x18x12 ins., in each sec., 5½ ft. dist., raised mound of earth 2 ft. high, 4½ ft. base over it.</p> <p>Land, mountainous. 50 chs. Rolling, 30 chs.</p> <p>Soil, 1st rate. Grass, fair.</p>  |   |
| <p>40.00</p> <p>79.71</p> <p>1.00</p> <p>39.85</p> <p>51.00</p> <p>52.00</p> <p>55.00</p> <p>79.71</p> | <p>East on random between secs. 28 and 33.</p> <p style="text-align: center;">Var. 21½° East.</p> <p>Set temporary ¼ sec. cor. and at</p> <p>Intersect N. and S. line, 47 lks. N. of cor. to secs. 27, 28, 33 and 34. Thence</p> <p>N.89°40'W. on true line between secs. 33 and 28.</p> <p style="text-align: center;">Var. 20° East.</p> <p>Dry bed of creek, S.W.</p> <p>Set basalt stone, 18x7x7 ins., 12 ins. in the ground for ¼ sec. cor. marked ¼ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it.</p> <p>Spring, N.W.</p> <p>Dry bed of creek, N.W.</p> <p>Summit ridge, N.W.</p> <p>Cor. to secs. 28, 29, 32 and 33.</p> <p>Land, mostly level.</p> <p>Soil, fine. No grass.</p> <p>Good farming land.</p> <p style="text-align: right;">August 1, 1887.</p> | <p></p> <p></p> <p></p> <p></p> <p></p> <p></p> <p></p> <p></p> <p>+60</p>                            |
| <p>10.00</p> <p>12.50</p> <p>15.00</p> <p>23.50</p> <p>40.00</p>                                       | <p>North between secs. 28 and 29.</p> <p style="text-align: center;">Var. 21½° East.</p> <p>Creek bottom</p> <p>Creek, 4 lks., N.60°W.</p> <p>Leave bottom and ascend.</p> <p>Top of rimrock.</p> <p>Set stone, 12x12x10 ins., 8 ins. in the ground, for ¼ sec. cor. marked ¼ on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., raised mound of earth</p>   | <p></p> <p></p> <p></p> <p></p> <p></p> <p></p> <p></p> <p></p> <p>-50</p> <p></p> <p></p> <p>+40</p> |