

Subdivisions of T. 1 N., R. 33 E.

Chains	<p>N.E., R 33 E S 16 on S.E., S 17 on S.W. and S 8 on N.W. faces with 4 notches on S. and E. edges, and dug pits, 18x18x12 ins., in each sec. $5\frac{1}{2}$ ft. dist., and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base around post.</p> <p>Land, level.</p> <p>Soil, 2nd rate.</p> <p>Very little grass. Some alkali.</p>
	<p>East on random between secs. 9 and 16.</p> <p style="text-align: center;">Var. 20° East.</p> <p>Set temporary $\frac{1}{4}$ and 1/16 sec. cors. at 20, 40 and 60 chains and at</p> <p>79.92 Intersect N. and S. line, 37 lks. N. of cor. to secs. 9, 10, 15 and 16. Thence</p> <p>N.89°44'W. on true line between secs. 9 and 16.</p> <p style="text-align: center;">Var. same.</p>
19.98	<p>Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>
39.96	<p>Set charred stake, 12 ins. in the ground, for $\frac{1}{4}$ sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on N. face.</p>
59.94	<p>Deposited charred stake 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
78.00	<p>Wagon road, N.W.</p>
79.92	<p>Cor. to secs. 8, 9, 16 and 17.</p> <p>Land, level.</p> <p>Soil, 1st rate. Poor grass.</p>