

Subdivisions of T. 1 N., R. 33 E.

Chains	S.89°55'W. on true line between secs. 17 and 20. Var. 23° East.	
39.87	Set basalt stone, 12x8x8 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
67.00	Dry gulch, N.W.	-50
79.75	Cor. to secs. 17, 18, 19 and 20. Land, level. Grass scarce. Soil, 1st rate. Uncultivated.	
	West on true line between secs. 18 and 19. Var. 20° East.	
25.00	Descend hill.	
27.00	Bottom hill.	-75
40.00	Set stone, 12x12x12 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of cor., $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base with earth over it.	
78.00	Intersect W. bdy. Township, 172 lks. N. of cor. to secs. 13 and 24, T. 1 N., R. 32 E. and set basalt stone, 10x8x7 ins., 7 ins. in the ground for closing cor. to secs. 18 and 19, marked C C on E. face with 3 notches on N. and S. faces. Dug pits, 18x18x12 ins., N. E. and S., $5\frac{1}{2}$ ft. dist. and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it. Land, rolling. Soil, 2nd rate. Grass not good. Some alkali.	
	North between secs. 17 and 18. Var. 20° E.	
27.50	Gulch and gravel bed, N.W.	
40.00	Set basalt stone, 12x10x8 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist. and raised mound	