

Subdivisions of T. 1 N., R. 33 E.

Chains	<p>Land, level.</p> <p>Soil, 1st rate. Grass scarce.</p>
	<p>West on true line between secs. 7 and 18.</p> <p style="text-align: center;">Var. 22° East.</p>
16.60	Dry ditch or bed of creek, N.W.
20.00	<p>Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>
22.70	Dry bed of creek, N.W.
40.00	<p>Deposited charred stake, 12 ins. in the ground for ¼ sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked ¼ S on N. face.</p>
43.50	Wagon road, N.W.
60.00	<p>Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>
63.70	Trail, N.W.
75.50	Ravine, N.W.
77.53	<p>Intersect W. bdy. Township, 215 lks. N. of cor. to secs. 12 and 13, T. 1 N., R. 32 E. and set basalt stone, 16x10x8 ins., 12 ins. in the ground for closing cor. to secs. 7 and 18 marked C C on E. face with 4 notches on S. and 2 notches on N. faces. Dug pits, 18x18x12 ins., N. E. and S. of stone, 5½ ft. dist. and raised mound of earth 1½ ft. high, 3½ ft. base over it.</p>
	<p>Land, level.</p> <p>Soil, good. Very little grass. Not cultivated.</p>