

Sub-Subdivisions of T. 1 N., R. 33 E.

Chains	base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
39.95	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{4}$ S on N. face.
59.92	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
79.90	$\frac{1}{4}$ sec. cor. between secs. 2 and 3. Land, rolling. Soil, 1st rate. Grass, fair.
	East on random through N. $\frac{1}{2}$ of sec. 2. Var. $20\frac{1}{2}^{\circ}$ East. Commencing at 1/16 sec. cor., 20 chains N. of $\frac{1}{4}$ sec. cor. between secs. 2 and 3. Set temporary 1/16 sec. cors. at 20, 40 and 60 chains and at
79.95	Intersect E. bdy, 28 lks. N. of 1/16 sec. cor. between secs. 1 and 2. Thence N. $89^{\circ}48'$ W. on true line. Var. 20° East. Ascend.
10.00	Summit hill.
19.98	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.