

Sub-Subdivisions of T. 1 N., R. 33 E.

Chains	Set temporary 1/16 sec. cors. at 20, 40 and 60 chains and at
79.95	Intersect E. bdy., 40 lks. N. of 1/16 sec. cor. between secs. 9 and 10. Thence N.89°43'W. on true line.
	Var. same.
19.98	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of cor., 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
30.50	Dry ditch, N.W.
39.97	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 12 ins. in the ground marked 1/16 S on N. face.
50.70	Wagon road, N.
59.96	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
79.95	1/16 sec. cor. between secs. 8 and 9. Land, level. Soil, 1st rate. Grass, good.
	East on random through center of sec. 9. Commencing at ¼ sec. cor. between secs. 8 and 9. Var. 20° East.
	Set temporary ¼ and 1/16 sec. cors. at 20, 40 and 60 chains and at
80.00	Intersect E. bdy., 42 lks. N. of ¼ sec. cor. between secs. 9 and 10. Thence