

Sub-Subdivisions of T. 1 N., R. 33 E.

Chains	N.89°42'W. on true line. Var. same.
8.25	Dry ditch, N.E.
18.50	Same, N.W.
20.00	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
40.00	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked ¼ S on N. face.
50.70	Wagon road, course N.E.
60.00	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
80.00	¼ sec. cor. between secs. 8 and 9. Land, level. Soil, 1st rate. No grass.
	East on random through N.½ of sec. 9. Commencing at 1/16 sec. cor., 20 chains N. of ¼ sec. cor. between secs. 8 and 9, set temporary 1/16 sec. cors. at 20, 40 and 60 chains and at
79.90	Intersect E. bdy., 40 lks. N. of sec. cor. between secs. 9 and 10. Thence N.89°43'W. on true line. Var. same.
19.97	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake,