

## Sub-Subdivisions of T. 1 N., R. 33 E.

Chains	
	base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
21.50	Fence and leave field and ditch, course S.E.
40.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
60.00	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
80.00	1/16 sec. cor. between secs. 4 and 5. Land, level. Soil, 1st rate. Grass, good.
	East on random through center of sec. 4. Commencing at ¼ sec. cor. between secs. 4 and 5. Var. 20° E. Set temporary ¼ and 1/16 sec. cors. at 20, 40 and 60 chains and at
79.95	Intersect E. bdy., 44 lks. N. of ¼ sec. cor. between secs. 3 and 4. Thence N.89°41'W. on true line. Var. same.
19.85	Dry ditch, course N.W.
19.99	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.