

## Sub-Subdivisions of T. 1 N., R. 33 E.

Chains 80.04	$\frac{1}{4}$ sec. cor. between secs. 7 and 8.
	Land, mostly level.
	Soil, 1st rate. No grass.
	October 30, 1887.
	East on random through N. $\frac{1}{2}$ of sec. 8.
	Var. $20\frac{1}{2}^{\circ}$ East.
	Commencing at 1/16 sec. cor. between secs. 7 and 8.
	Set temporary 1/16 sec. cors. at 20, 40 and 60 chains and at
79.96	Intersect E. bdy., 30 lks. N. of 1/16 sec. cor. between secs. 8 and 9. Thence
	N. $89^{\circ}47'W.$ on true line.
	Var. same.
19.99	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
39.98	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
59.97	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
79.96	1/16 sec. cor. between secs. 7 and 8.
	Land, level.
	Soil, fair. Grass, poor. Not cultivated.
	October 30, 1887.