

Sub-Subdivisions of T. 1 N., R. 33 E.

Chains	ins. square, 12 ins. in the ground marked 1/16 S on N. face.
40.50	Dry ditch, course N.W.
54.00	Dry bed of creek, N.W.
60.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground for 1/16 sec. cor. marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it.
77.49	Intersect W. bdy., Township, 17.60 chs. S. of ¼ sec. cor. on E. bdy. secs. 12, T. 1 N., R. 32 E. and set basalt stone, 12x8x10 ins., 8 ins. in the ground for 1/16 sec. closing cor. marked 1/16 C C on E. face. Dug pits, 18x18x12 ins., N. E. and S. of stone, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it. Land, slightly rolling. Soil, 1st and 2nd rate. Some alkali. Vegetation eaten off closely.
	West through center of sec. 7. Var. 21½° East. Commencing at ¼ sec. cor. between secs. 7 and 8.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
40.00	Set stone, 9x8x10 ins., 6 ins. in the ground, for ¼ sec. cor. marked ¼ on N. face, raised mound of stone. 1½ ft. high, 3½ ft. base over it.
44.00	Gulch, course N.W.
60.00	Set charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
77.45	Intersect W. bdy. Township, 225 lks. N. of ¼ sec. cor.