

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 15
59.77	Setting temporary 1/16 sec. corner at every 20 chains at
	Intersect the 1/16 sec. corner, 20 chs. S., from the line
	between secs. 10 and 15.
	Thence I run
	N.89°43'W. on true line in sec. 15.
	Var. 20°E.
19.93	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for
	1/16 sec. corner marked 1/16 on N. face. Dug pits,
	18x18x12 ins., E. and W. of stone, 5½ ft. dist., and
	raised a mound of earth 1½ ft. high, 3½ ft. base over
	it.
37.00	Gulch, course N.W.
39.85	Set a basalt stone, 14x10x5 ins., 10 ins. in the ground,
	for 1/16 sec. corner, marked 1/16 on N. face. Dug
	pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist.,
	and raised a mound of earth 1½ ft. high, 3½ ft. base
	alongside.
40.20	Trail, course N.W.
59.77	To the 1/16 sec. corner, 20 chains South of the corner to
	secs. 9, 10, 15 and 16.
	Land, mostly level.
	Soil, 1st rate.
	Grass and wild alfalfa.
	From the 1/16 sec. corner, 20 chs. S. of ¼ sec. corner
	between secs. 10 and 15.
	I run
	South on true line in the middle of sec. 15.
	Var. 21°E.
20.00	Set basalt stone, 10x7x6 ins., 7 ins. in the ground, for
	¼ sec. corner, marked ¼ on W. face. Dug pits, 18x18x12
	ins., N. and S. of stone, 5½ ft. dist., and raised a
	mound of earth 1½ ft. high, 3½ ft. base over it.
	Thence I run
	N.89°40'W. on random line through sec. 15.
	Var. 20°E.