

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 17
60.00	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
61.00	Road, course N.20°W.
80.00	The corner to secs. 7, 8, 17 and 18, which is a basalt stone, 9x8x7 ins., 6 ins. in the ground, marked with 4 notches on S. and 5 notches on E. edges with pits, 18x18x12 ins., in each sec., 5½ ft. dist., and mound of earth 2 ft. high, 4½ ft. base over it.
	Land, gently rolling. Soil, 2nd rate. Very little grass and weeds.
	From the 1/16 sec. corner, 20.00 chains N. of the corner to secs. 17, 18, 19 and 20.
	I run
	S.89°48'E. on random line through the S.½ of sec. 17.
	Var. 20°E.
	Setting temporary 1/16 sec. corner at 20, 40 and 60 chains and at
80.00	Intersect the East bdy. of sec. 17, 6 lks. S. of 1/16 sec. cor. between secs. 16 and 17.
	Thence I run
	N.89°51'W. on true line through section 17.
	Var. 19°E.
5.00	Ditch, course N.W.
20.00	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. corner. Dug pits, 18x18x12 ins., E. and W. of corner, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit drove a stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.