

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 17
40.00	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. corner. Dug pits, 18x18x12 ins., E. and W. of corner, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
45.50	Gulch, course N.W.
60.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
80.00	To 1/16 sec. corner. Land, mostly level. Soil, 2nd rate. Grass and weeds.
From the ¼ sec. corner between secs. 17 and 18.	
I run	
S.89°48'E. on random line through the center of sec. 17. Var. 20°E.	
Setting temporary 1/16 and ¼ sec. corners at 20, 40 and 60 chains and	
80.00	Intersect the East boundary of sec. 17, 5 lks. South of ¼ sec. corner between secs. 16 and 17. Thence I run N.89°50'W. on true line through the center of sec. 17. Var. 21°30'E.
20.00	Set a basalt stone, 11x7x6 ins., 7 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it.
40.00	Deposited a marked stone, 12 ins. in the ground, for ¼ sec. cor. Dug pits, 18x18x12 ins., E. and W. of corner, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face.