

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains 60.00	<p style="text-align: center;">Sec. 17</p> <p>Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist. and raised a mound of earth 1½ ft. high, 3½ ft. base over it.</p>
78.00	Gulch, course N.W.
80.00	<p>To the ¼ sec. corner between secs. 17 and 18.</p> <p>Land, rolling and level, mixed.</p> <p>Soil, 2nd rate.</p> <p>Grass and wild alfalfa.</p>
	<p>From the 1/16 sec. corner, 20 chains N. of the ¼ sec. cor. between secs. 17 and 18.</p> <p>I run</p> <p>S.89°48'E. on a random line through the N.½ of sec. 17.</p> <p style="text-align: center;">Var. 19°15'E.</p> <p>Setting temporary 1/16 sec. corner at every 20, 40 and 60 chs., and at</p>
80.10	<p>Intersect East boundary of sec. 17, 8 lks. S. of 1/16 sec. corner between secs. 16 and 17.</p> <p>Thence I run</p> <p>N.89°51'W. on true line through the N.½ of sec. 17.</p> <p style="text-align: center;">Var. 20°East.</p>
20.02	<p>Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face; dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.</p>
40.05	<p>Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.</p>
60.07	<p>Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and</p>