

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 18
	<p>From the closing corner to secs. 7 and 18, on West boundary of Township, which is a basalt stone, 16x10x8 ins., 12 ins. in the ground marked C C on E. face and 4 notches on S. and 2 notches on N. edges with pits, 18x18x12 ins., N., E. and S. of stone, 5½ ft. dist., and mound of earth 2½ ft. high, 4½ ft. base over it. I marked stone D R on the E. face.</p>
	<p>I run South on the W. bdy. of sec. 18.</p>
	<p>Var. 21°30'E.</p>
2.15	<p>To the old corner to secs. 12 and 13, T. 1 N., R. 32 E., which is a basalt stone, 9x8x7 ins., 6 ins. in the ground, marked with 3 notches on N. and S. edges. Pits in each section 5½ ft. dist., and mound of earth alongside. I marked D R on E. face.</p>
22.75	<p>Top of hill.</p>
27.75	<p>Gulch, course W.</p>
40.00	<p>Set a stone, 9x8x7 ins., 6 ins. in the ground, for closing ¼ sec. corner to S. 18, T. 1 N., R. 33 E., marked C C ¼ on E. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ feet high, 3½ ft. base over it.</p>
41.95	<p>Intersect the ¼ sec. corner on the E. bdy. of sec. 13, T. 1 N., R. 32 E., which is a basalt stone, 10x10x8 ins., 7 ins. in the ground marked ¼ on W. face. Pits, 18x18x12 ins., N. and S. of corner, 5½ ft. dist., and mound of earth 1½ ft. high, 3½ ft. base over it. I marked stone D R on East face.</p>
50.75	<p>Top of hill.</p>
55.50	<p>Dry gulch, course W.</p>
80.00	<p>The closing corner to secs. 18 and 19, T. 1 N., R. 33 E. Land, rolling. Soil, 3rd rate. Very little grass.</p>