

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 19
40.00	The old $\frac{1}{4}$ sec. corner, which is a basalt stone, 12x9x4 ins., 6 ins. in the ground, marked $\frac{1}{4}$ on W. face. Pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist., and mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
60.00	Set a basalt stone, 11x8x6 ins., 7 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
80.00	To corner to secs. 17, 18, 19 and 20. Land, level. Soil, ashy; not cultivated. Grass and weeds.
From the $\frac{1}{4}$ sec. corner between secs. 19 and 30.	
I run	
North on true line in sec. 19.	
Var. $20\frac{1}{2}^{\circ}$ E.	
20.00	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face, and raised a mound of stone over it. Pits impracticable. Land, level and barren. Soil, ashy.
From the 1/16 sec. corner, 20 chains N. of corner to secs. 19, 20, 29 and 30.	
I run	
West on random line in sec. 19.	
Var. $20\frac{1}{2}^{\circ}$ E.	
20.00	Set temporary 1/16 sec. corner.
40.00	Intersect the 1/16 sec. corner.
Thence I run	
East on true line in sec. 19.	
Var. 21° E.	
2.00	Trail, course S.W.
20.00	Set basalt stone, 11x9x6 ins., 7 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits,