

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 19
	<p>From the 1/16 sec. corner, 18 chs. E. from the N.W. corner of sec. 19.</p> <p>I run</p> <p>South on true line in sec. 19.</p> <p style="text-align: center;">Var. 21°E.</p>
20.00	<p>Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it.</p> <p>Land, rolling.</p> <p>Soil, 3rd rate.</p> <p>Very little grass.</p>
	<p>From the 1/16 sec. corner, 20 chs. N. of the ¼ sec. corner between secs. 19 and 20.</p> <p>I run</p> <p>West on a random line through the N. ½ of sec. 19.</p> <p style="text-align: center;">Var. 21°00' East.</p> <p>Setting temporary corners at 20 and 40 chains, and at</p>
60.00	<p>Intersect the 1/16 sec. corner at stone.</p> <p>Thence I run</p> <p>East on true line through the N. ½ of sec. 19.</p>
20.00	<p>Deposited charred stake, 12 ins. in the ground, for 1/16 sec. corner. Dug pits, 18x18x12 ins., E. and W. of corner, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it. In East pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
34.50	<p>Draw, course N.</p>
40.00	<p>Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.</p>
60.00	<p>To the 1/16 sec. corner between secs. 19 and 20.</p>