

Subdivisions and Allotments of T. 1 N., R. 33 E.

| | |
|--------|--|
| Chains | <p style="text-align: center;">Sec. 21</p> <p>N.89°34'W. on true line through the center of sec. 21.</p> <p style="text-align: center;">Var. 21°E.</p> |
| | Descend. |
| 19.95 | <p>Gulch, course N.W.</p> <p>Water in holes.</p> |
| 20.00 | <p>Set basalt stone, 10x9x6 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face, and raised a mound of stone alongside. Pits impracticable.</p> |
| 29.75 | Road, course N. and S. |
| 40.00 | <p>Set basalt stone, 10x8x7 ins., 6 ins. in the ground, for 1/4 sec. corner marked 1/4 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 1/2 ft. dist., and raised a mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.</p> <p>Descend to</p> |
| 51.50 | Road, course N. and S. |
| 60.00 | <p>Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 1/2 ft. dist., and raised a mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.</p> |
| 80.00 | <p>To the 1/4 sec. corner between secs. 20 and 21.</p> <p>Land, rolling.</p> <p>Soil, 2nd and 3rd rate.</p> <p>Grass, good on foot hills.</p> |
| | <p>From the 1/16 sec. corner, 20 chs. N. of 1/4 sec. cor. between secs. 20 and 21.</p> |
| | I run |
| | <p>S.89°45'E. on a random line through N. 1/2 of sec. 21.</p> <p style="text-align: center;">Var. 21°E.</p> |
| 80.00 | <p>Setting temporary corner at 20, 40 and 60 chains, and at Intersect East boundary of sec. 21, 15 lks. North of 1/16 sec. corner, 20 chains N. of 1/4 sec. corner between secs. 21 and 22.</p> <p>Thence I run</p> |