

East Boundary of T. 1 N., R. 34 E.

| | |
|--------|--|
| Chains | |
| 40.00 | Set post for $\frac{1}{4}$ sec. corner, from which A fir, 14 ins. diam., bears N.60°W., 25 lks. |
| 44.50 | To spring of good water. |
| 80.00 | Set post for corner to secs. 12, 13, 7 and 18, from which A fir, 10 ins. diam., bears N.50°W., 20 lks. " " 10 " " " S.39°E., 16 lks. |
| | Table land. Soil, 1st rate. Good grass. Pine and fir timber. |
| | North on East boundary of sec. 12. Var. 21° E. |
| 10.50 | McKay creek, 20 lks., flows S.W. |
| 40.00 | Set post and raised stone mound for $\frac{1}{4}$ sec. corner. |
| 55.50 | Brook, 8 lks. wide, flows S.E. |
| 80.00 | Set post and raised stone mound for cor. to secs. 1, 12, 6, 7. Land, mountainous. Soil, 1st rate. Good grass. Pine and fir timber. |
| | North on East boundary sec. 1. Var. 21° E. |
| 40.00 | Set post and raised stone mound for $\frac{1}{4}$ sec. cor. |
| 55.50 | LaGrande and Pendleton Wagon road, course NW. and SE. |
| 80.00 | Set post for corner to Townships 1 and 2 North, Ranges 34 and 35 East, from which A fir, 10 ins. diam., bears N.80°E., 10 lks. " " 8 " " " N.70°W., 12 lks. |
| | Land, mountainous. Soil, 2nd rate. Good grass. Pine and fir timber. |