

## Subdivisions of T. 1 N., R. 34 E.

Chains 80.00	Set basalt stone, 18x18x10, for corner to secs. 29, 30, 31 and 32. Land, mountainous. Soil, 2nd rate. Some grass. Pine timber scattering.
	East on true line on South boundary of section 29. Var. 21°30' East.
40.00	Set basalt stone, 14x10x10, for $\frac{1}{4}$ sec. corner.
80.00	Set basalt stone, 16x14x10, for corner to secs. 28, 29, 32 and 33. Corner stands in creek bottom. Land, mountainous. Soil, 2nd rate. Some grass. Scattering pine and fir timber.
	North between secs. 28 and 29. Var. 22° East.
40.00	Set basalt stone, 12x12x12, for $\frac{1}{4}$ sec. corner.
80.00	Set basalt stone, 17x14x9, for corner to secs. 28, 29, 20 and 21. Land, mountainous. Soil, 2nd rate. Good grass. Some pine and fir timber.
	North between secs. 20 and 21. Var. 21° 30' East.
40.00	Set basalt stone, 14x14x7, for $\frac{1}{4}$ sec. corner.
80.00	Set post for corner to secs. 20, 21, 16 and 17, from which A pine, 30 ins. diam., bears N.45° E., 55 lks. " " 36 " " " S.25°W., 40 lks. Land, mountainous. Soil, 2nd rate. Pine timber scattering. Good grass.
	North between secs. 16 and 17. Var. 20° East.