

## Subdivisions of T. 1 N., R. 34 E.

Chains	West on random between secs. 18 and 19.
40.00	Set temporary $\frac{1}{4}$ section corner.
80.20	Intersected N. and S. line, 15 lks. S. of cor. S.89°54'E. on true line.
40.20	Set basalt stone, 16x12x10, for $\frac{1}{4}$ section corner.
80.20	To corner.
	Land, hilly.
	Soil, 2nd rate.
	Good grass. Some pine and fir timber.
	North between secs. 17 and 18.
40.00	Set post and made stone mound for $\frac{1}{4}$ section corner.
80.00	Set basalt stone, 18x14x10, for cor. to 7, 8, 17 and 18.
	Land, hilly.
	Soil, 2nd rate.
	Good grass. Some pine timber.
	May 11, 1871.
	East on random between secs. 8 and 17.
	Var. 20° East.
40.00	Set temporary $\frac{1}{4}$ sec. corner.
80.06	Intersected N. and S. line, 20 lks. S. of cor. S.89°52'W. on true line.
40.03	Set basalt stone, 14x14x12, for $\frac{1}{4}$ section corner.
80.06	To corner.
	Land, hilly.
	Soil, 2nd rate.
	Good grass. Some pine and fir timber.
	West on random between secs. 7 and 18.
40.00	Set temporary $\frac{1}{4}$ sec. corner.
80.14	Intersected N. and S. line, 10 lks. N. of cor. N.89°56'E. on true line.
40.14	Set basalt stone, 14x14x8, for $\frac{1}{4}$ section corner.
80.14	To corner.
	Land, hilly.