

Subdivisions of T. 1 N., R. 34 E.

Chains

Land, hilly.

Soil, 2nd rate.

Good grass.

May 12, 1871.

Base Line of T. 1 N., R. 34 E.
 Surveyed by Currin and Noland under special contract.
 Dated May 4, 1887.

Commencing at cor. to Tps. 1 N., Rgs. 33 and 34 East

I ran

East on random on S. bdy. of T. 1 N., R. 34 E.

Var. $21\frac{3}{4}^{\circ}$ East.

Set temporary secs. and $\frac{1}{4}$ sec. cors. at 40 and 80 chains
 and at 6 miles and 2.74 chains a point 84 lks. S. of
 cor. to secs. 31 and 36, Tps. 1 N., Rgs. 34 and 35
 East, which is a post, 4 ft. long, 4 ins. square, still
 standing but badly decayed. Marked T.1 N., R.34 E. Sec. 36
 on N.W., T.1 N., R.35 E. Sec. 31 on N.E. faces with mound
 of stone alongside.

I reestablish this cor. by setting post, 4 ft. long,
 4 ins. square, 24 ins. in the ground, for cor. to
 T. 1 N., Rgs. 34 and 35 E. marked S C T 1 N on N.,
 R 35 E S 31 on E., and R 34 E S 36 on W. faces with 6
 notches on N. E. and W. edges, and raised mound of
 stone $2\frac{1}{2}$ ft. high, $5\frac{1}{2}$ ft. base over it.

June 10, 1887.

Thence S. $89^{\circ}54'W.$ on true line, S. bdy sec. 36., T. 1 N.,
 R. 34 East.

Var. $23\frac{1}{2}^{\circ}$ East.

12.00 Descend steep mountain side.

40.00 Set basalt stone, 18x9x6 ins., in mound of stone, $2\frac{1}{2}$ ft.
 base, $5\frac{1}{2}$ ft. high, on S.W. side of hill. Pits
 impracticable, marked stone S C $\frac{1}{4}$ on N. face.

44.50 N.fork of McKays creek, 20 lks. wide, runs N.W.; ascend.

65.00 Gulch and leave timber.

Ascend.