

Base Line of T. 1 N., R. 34 E.

Chains

General Description

This portion of the Base Line passes over very rough breaks and canyons adjoining at high plateau. Also crosses North fork of McKay creek. Soil, rocky but produces good bunch grass. Good pine timber in McKay Creek Canyon but it is scarce on the higher land.

Exterior Lines of T. 1 N., R. 34 E.
 Surveyed by Currin and Noland under special contract.
 Dated May 4, 1887.

(North Boundary)

Beginning at the cor. to Tps. 1 and 2 N., R. 33 and 34 E.

I run

East on random between Tps. 1 and 2 N., R. 34 E. setting temporary $\frac{1}{4}$ sec. and sec. cors. at each 40 and 80 chs. and at 6 miles and 4 chs. intersect E. bdy., 390 lks.

S. of cor. to Tps. 1 and 2 N., R. 34 and 35 E.

Random surveyed August 8, 1887.

Thence I run S.89°32'W. on true line on N. bdy. sec. 1

Var. 20°E.

Enter timber.

1.50 Hollow, course N.

37.50 " " "

40.00 Set basalt stone, 12x8x8 ins., 8 ins. in the ground for

$\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, from which

A pine, 14 ins. in diam., bears N.75°E., dist. 122 lks. marked $\frac{1}{4}$ S B T.

A pine, 18 ins. in diam., bears S.63°E., dist. 73 lks. mkd. $\frac{1}{4}$ S B T.

49.00 Wagon road, course N.W.

80.00 Set a basalt stone, 16x14x14 ins., 11 ins. in the ground,

for cor. to secs. 1, 2, 35 and 36 marked 1 notch on E.

and 5 on W. edges, from which

A pine, 36 ins. in diam., bears N. 12° W., dist. 25 lks. marked T 2 N R 34 E Sec. 35 B T.

No other trees in limits.