

North Boundary of T. 1 N., R. 34 E.

| | |
|-----------------|--|
| Chains 40.00 | Set a basalt stone, 12x8x8 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Raised mound of stone alongside. Pits impracticable. |
| 44.00 | Gulch, course S. |
| 47.50 | Summit. |
| 51.75 | Gulch, course S. |
| 80.00 | Set a basalt stone, 14x10x8 ins., 10 ins. in the ground, for cor. to secs. 3, 4, 33 and 34, marked 3 notches on E. and W. edges. Raised md. of stone alongside. Pits impracticable. |
| | Land, mountainous. 80.00 chs. |
| | Soil, rocky, 4th rate. |
| | No timber. Poor grass. |
| | South 89°32'W. on N. bdy. sec. 4. Var. 20°45'E. |
| 11.75 | Canyon, course N.W. |
| 20.50 | Summit, course N. |
| 26.00 | Canyon, " " |
| 40.00 | Set a basalt stone, 10x8x8 ins., 7 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, from which A pine 20 ins. in diam., bears N.70°E., dist. 255 lks. marked $\frac{1}{4}$ S B T. A pine, 20 ins. in diam., bears S.75°E., dist., 294 lks. marked $\frac{1}{4}$ S B T. |
| 56.25 | Gulch, course N. |
| 68.50 | Trail on Summit, course N. |
| 80.00 | To a stone, 36x18x20 ins., above ground, which I marked 4 notches on E. and 2 on W. edges and a cross (x) at exact cor. point, for cor. to secs. 4, 5, 32 and 33. Raised stone md. alongside. Pits impracticable. |
| | Land, mountainous. 80 chs. |
| | Soil, 3rd rate. |
| | No timber. Good grass. |