

## West Boundary of T. 1 N., R. 35 E.

Chains	
	A fir, 10 ins. in diam., bears S.30°W., dist. 28 lks. marked $\frac{1}{4}$ S B T.
47.75	Brook, 10 lks. wide, course W. Leave timber.
80.00	Set a basalt stone, 10x10x8 ins., 7 ins. in the ground, for cor. to secs. 13, 18, 19 and 24, marked 3 notches on N. and S. edges, from which A pine, 10 ins. in diam., bears N.50°E., dist. 217 lks. marked T 1 N R 35 E S 18 B T. A pine, 6 ins. in diam., bears S.85°E., dist. 300 lks. marked S 19 B T. No other tree in limits. Raised mound of stone alongside. Pits impracticable. Land, mountainous. 80 chs. Soil, rocky, 4th rate. Timber, pine and fir. 47.75 chs. Poor bunch grass.
	North between secs. 13 and 18. Var. 18°E.
21.40	A forked pine, 2 ft. in diam.; descend.
40.00	Set a post, 36x3x3 ins., 2 ft. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S on W. face, from which A pine, 28 ins. in diam., bears N.10°E., dist. 62 lks., marked $\frac{1}{4}$ S B T. A pine, 12 ins. in diam., bears S.30°W., dist. 30 lks., marked $\frac{1}{4}$ S B T.
71.00	Bluff.
80.00	Set a basalt stone, 20x10x8 ins., 15 ins. in the ground, for cor. to secs. 7, 12, 13 and 18, marked 4 notches on S. and 2 notches on N. edges. Raised a md. of stone alongside. Pits impracticable. Land, mountainous. 80 chs. Soil, rocky, 4th rate. Scattering pine timber in canyons. Poor bunch grass.