

## West Boundary of T. 1 N., R. 35 E.

Chains	<p>North between secs. 7 and 12.</p> <p style="text-align: center;">Var. 17°E.</p> <p>8.00 Branch of McKay creek, 6 lks. wide, S.W.</p> <p>40.00 Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for <math>\frac{1}{4}</math> sec. cor. marked <math>\frac{1}{4}</math> on W. face. Raised md. of stone alongside. Pits impracticable.</p> <p>41.00 Summit of hill.</p> <p>47.50 Canyon, course S.E.</p> <p>80.00 Set a post, 48x4x4 ins., 24 ins. in the ground, for cor. to secs. 1, 6, 7 and 12, marked T 1 N S 1 on N.W., S 6 on N.E., R 35 E S 7 on S.E., R 34 E S 12 on S.W. faces and 5 notches on S. and 1 on N. edges, from which</p> <p style="padding-left: 40px;">A pine, 18 ins. in diam., bears N.50°E., dist. 10 lks. marked T 1 N R 35 E S 6 B T.</p> <p style="padding-left: 40px;">A pine, 10 ins. in diam., bears S. 52°E., dist. 54 lks. marked S 7 B T.</p> <p style="padding-left: 40px;">A pine, 20 ins. in diam., bears S.80°W., dist. 7 lks., marked R 34 E S 12 B T.</p> <p style="padding-left: 40px;">A pine, 18 ins. in diam., bears N.82°W., dist. 38 lks. marked S 1 B T.</p> <p>Land, mountainous. 80 chs.</p> <p>Soil, rocky, 4th rate.</p> <p>Scattering pine timber. Good bunch grass.</p>
	<p>North between secs. 1 and 6.</p> <p style="text-align: center;">Var. 20°E.</p> <p>40.00 Set a basalt stone, 10x8x6 ins., 7 ins. in the ground, for <math>\frac{1}{4}</math> sec. cor., marked <math>\frac{1}{4}</math> on W. face, from which</p> <p style="padding-left: 40px;">A pine, 26 ins. in diam., bears N.87°E., dist. 83 lks., marked <math>\frac{1}{4}</math> S B T.</p> <p style="padding-left: 40px;">A pine, 20 ins. in diam., bears S.35°W., dist. 115 lks. marked <math>\frac{1}{4}</math> S B T.</p> <p>53.00 Pendleton and LaGrande wagon road, E. and W.</p> <p>70.00 Spring.</p> <p>80.00 A pine tree, 20 ins. in diam., which I marked for cor. to Tps. 1 and 2 N., Rs. 34 and 35 E., T 1 N R 35 E S 6</p>