

Subdivisions of T. 1 N., R. 34 E.

Chains 80.35	To cor. to secs. 23, 24, 25 and 26. Land, rolling. Scattering pine timber. Soil, rocky, 2nd rate.
12.75 40.00 53.00 80.00	N. between secs. 23 and 24. Var. 20° E. Shallow gulch, bears W. Set basalt stone, 12x12x6 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face and raised mound of stone over it. Pits impracticable. Canyon, course N.W., with running water. Set stone, 18x12x6 ins., 14 ins. in the ground, for cor. to secs. 13, 14, 23 and 24, marked with 3 notches on S. and 1 notch on E. edges and raised a mound of stone over it. Pits impracticable. Land, rough and mountainous covered with scattering pine timber. 80 chs. Soil, 3rd rate.
40.00 80.54 40.27 75.00 80.54	East on random between secs. 13 and 24. Var. 24 $\frac{1}{2}$ ° E. Set temporary $\frac{1}{4}$ sec. cor. Intersect T. line, 54 lks. S. of cor. Thence I run S. 89° 37' W. on true line. Set a basalt stone, 18x10x10 ins., 14 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, raised a mound of stone over it. Pits impracticable. Begin to descend. To cor. of secs. 13, 14, 23 and 24. Land, rolling. Scattering pine timber. Good bunch grass. Soil, rocky, 3rd rate.
	North between secs. 13 and 14. Var. 24° 30' E.