

Subdivisions of T. 1 N., R. 34 E.

Chains	<p>Land, rolling with bunch grass, and scattering pine timber.</p> <p>Soil, 3rd rate.</p> <p style="text-align: center;">August 4, 1887.</p>
	<p>North on random between secs. 1 and 2.</p> <p style="text-align: center;">Var. 17°E.</p>
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.62	<p>Intersect T. line, 40 lks. W. of cor. to secs. 1, 2, 35 and 36. Thence I run S.17°W. on true line.</p>
8.00	Pendleton and LaGrande wagon road, course E. and W.
40.62	<p>Set a basalt stone, 12x8x7 ins., 8 ins. in the ground, marked $\frac{1}{4}$ on W. face, for $\frac{1}{4}$ sec. cor., from which A pine, 30 ins. diam., bears S.70°W., 25 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>No other trees within limits.</p> <p>Raised mound of stone over it. Pits impracticable.</p>
55.70	Timbered gulch, course S.E.
80.62	<p>To cor. secs. 1, 2, 11 and 12.</p> <p>Timber, good in sec. 1 and S.E.$\frac{1}{4}$ of sec. 2.</p> <p>Soil, 2nd rate.</p> <p>Land, rolling.</p>
	<p>From cor. to secs. 34 and 35 on S. bdy. of Township I run North between secs. 34 and 35.</p> <p style="text-align: center;">Var. 20°E.</p> <p>Descend into canyon.</p>
40.00	<p>Set post, 3 ft. long, 3 ins. square, 24 ins. in ground, marked $\frac{1}{4}$ S on W. face, for $\frac{1}{4}$ sec. corner. Raised mound of stone around it.</p>
56.80	North fork McKay creek, course W.
80.00	<p>Set basalt stone, 18x12x8 ins. 14 ins. in the ground, for cor. to secs. 26, 27, 34 and 35, marked one notch on S., two notches on E. edges. Raised mound of stone over it. Pits impracticable.</p>