

Subdivisions of T. 1 N., R. 34 E.

Chains	<p>marked $\frac{1}{4}$ on N. face, for $\frac{1}{4}$ sec. cor. Raised a mound of stone over it. Pits impracticable.</p> <p>54.50 Gulch, course S.</p> <p>70.00 Summit ridge, course S.</p> <p>80.00 To cor. to secs. 10, 11, 14 and 15.</p> <p>Land, rough and mountainous. 80 chs.</p> <p>Good bunch grass.</p> <p>Soil, 2nd rate.</p>
	<p>North between secs. 10 and 11.</p> <p style="text-align: center;">Var. 20°15'E.</p> <p>25.00 Summit of ridge.</p> <p>35.00 Canyon, course W.</p> <p>40.00 Set basalt stone, 9x8x7 ins., 6 ins. in the ground, marked $\frac{1}{4}$ on W. face, for $\frac{1}{4}$ sec. cor. Raised a mound of stone over it. Pits impracticable.</p> <p>65.25 Gulch, course W.</p> <p>67.50 Canyon, water in holes, course W.</p> <p>80.00 To a pine tree, 8 ins. diam., which I marked T 1 N R 34 E S 2 on N.E., Sec. 11 on S.E., S 10 on S.W., S 3 on N.W. faces with 5 notches on S. and 2 on E. edges, for corner to secs. 2, 3, 10 and 11, from which</p> <p style="padding-left: 40px;">A pine, 10 ins. diam., bears N.4°E., dist. 10 lks., marked S 2 T 1 N B T.</p> <p style="padding-left: 40px;">A pine, 20 ins. in diam., bears N.45°W., dist. 25 lks., marked S 3 B T.</p> <p style="padding-left: 40px;">A pine, 16 ins. in diam., bears ^{might be 92°} S.32°W., dist. 8 lks., marked S 10 B T.</p> <p style="padding-left: 40px;">A pine, 10 ins. in diam., bears S.3°E., dist., 7 lks., marked S 11 R 34 E B T.</p> <p>Land, mountainous. 80.00 chs.</p> <p>Some pine timber.</p> <p>Soil, 3rd rate.</p> <p style="text-align: right;">August 5, 1887.</p>