

Subdivisions of T. 1 N., R. 34 E.

Chains	
12.50	N. fork McKay Creek, 40 lks. wide, course W.
24.25	Leave Creek bottom; ascend.
40.00	Set basalt stone, 14x10x8 ins., 9 ins. in the ground, marked $\frac{1}{4}$ on W. face for $\frac{1}{4}$ sec. cor., raised mound of stone over it. Pits impracticable.
64.00	Top of ridge, shell rock bluff.
78.00	Head of canyon, course S.W.
80.00	Set a basalt stone, 10x8x7 ins., 7 ins. in the ground, marked 2 notches on S., 4 notches on E. edges, for cor. to secs. 20, 21, 28 and 29, from which A pine, 12 ins. diam., bears S.25°W., dist. 350 lks., marked S 29 B T. A pine, 10 ins. diam., bears S.4°E., 384 lks. dist., marked S 28 R 34 E B T. A pine, 10 ins. diam., bears N.33°E., dist. 236 lks., marked S 21 T 1 N B T. A pine, 10 ins. diam., bears N.37°W., dist. 272 lks., marked S 20 B T. Land, broken with deep canyons, mountainous 80 chs. Covered with bunch grass. Soil, 3rd rate.
	East on random between secs. 21 and 28. Var. 15°E.
40.00	Temporary $\frac{1}{4}$ sec. cor.
80.10	Intersect N. and S. line, 20 lks. N. of cor. to secs. 21, 22, 27 and 28. Thence I run N.89°51'W. on true line.
26.75	Gulch with some water, course S.
32.50	Summit of ridge, course S.
40.05	Set basalt stone, 10x8x6 ins., 7 ins. in the ground, marked $\frac{1}{4}$ on N. face, for $\frac{1}{4}$ sec. cor., raised mound of stone over it. Pits impracticable.
48.00	Gulch, course S.E.
80.10	To cor. to secs. 20, 21, 28 and 29. Land, mountainous. 80.10 chs. Soil, 3rd rate.