

## Subdivisions of T. 1 N., R. 34 E.

Chains	<p>A pine, 16 ins. diam., bears N.10°W., dist. 100 lks., marked <math>\frac{1}{4}</math> S B T.</p> <p>Raised mound of stone over it. Pits impracticable.</p> <p>60.25 Gulch, course N.</p> <p>79.70 To cor. of secs. 16, 17, 20 and 21.</p> <p>Land, rolling.</p> <p>Scattering pine timber.</p> <p>Soil, 3rd rate.</p>
	<p>North between secs. 16 and 17.</p> <p style="text-align: center;">Var. 19°25'E.</p>
30.50	Old wagon road, course S.W.
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in the ground, marked <math>\frac{1}{4}</math> S on W. face, for <math>\frac{3}{4}</math> sec. cor., from which</p> <p style="padding-left: 40px;">A pine, 28 ins. diam., bears N.50°W., dist. 57 lks., marked <math>\frac{1}{4}</math> S B T.</p> <p style="padding-left: 40px;">A pine, 24 ins. diam., bears N.15°E., dist. 40 lks., marked <math>\frac{1}{4}</math> S B T.</p>
41.50	Dry gulch, course E.
57.60	Top of ridge.
79.50	Canyon, course E.
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 2 ft. in ground, for corner to secs. 8, 9, 16 and 17, marked Sec. 9 T 1 N on N.E. face, S 16 on S.E. face, R 34 E S 17 on S.W. face, Sec. 8 on N.W. face, and 4 notches on S. and 4 notches on E. edges, from which</p> <p style="padding-left: 40px;">A fir, 6 ins. diam., bears N.50°W., dist. 10 lks., marked S 8 R 34 E B T.</p> <p style="padding-left: 40px;">A fir, 10 ins. diam., bears S.20°E., dist. 110 lks., marked S 16 T 1 N B T.</p> <p style="padding-left: 40px;">No trees with limits.</p> <p style="padding-left: 40px;">Raised a mound of stone alongside.</p> <p>Land, mountainous, 40 chs, balance rolling.</p> <p>Scattering pine timber.</p> <p>Soil, 3rd rate.</p>
	August 8, 1887.