

Subdivisions of T. 1 N., R. 34 E.

Chains	<p>Land, mountainous. 80.00 chs. Scattering pine timber in canyons. Soil, 4th rate.</p>
	<p>East on random between secs. 4 and 9. Var. 20°E.</p>
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.35	Intersect N. and S. line, 25 lks. S. of cor. to secs. 3, 4, 9 and 10. Thence I run S.89°49'W. on true line.
6.50	Gulch, course W.
40.17	Set a basalt stone, 10x12x6 ins., 8 ins. in the ground, marked $\frac{1}{4}$ on N. side, for $\frac{1}{4}$ sec. cor. Raised a mound of stone over it. Pits impracticable.
80.35	To cor. to secs. 4, 5, 8 and 9. Land, mountainous. 40 chs. Good bunch grass. Soil, 3rd rate.
	<p>North on random between secs. 4 and 5. Var. 20°E.</p>
40.00	Set temporary $\frac{1}{4}$ sec. cor.
81.06	Intersect T. line, 21 lks. W. of cor. to secs. 4, 5, 32 and 33. Thence I run S.9°W. on true line.
23.50	Canyon, course W.
27.00	Point, course W.
34.50	Canyon, course N.W.
41.06	Set a post, 3 ft. long, 3 ins. sq., 12 ins. in ground, marked $\frac{1}{4}$ S on W. face, for $\frac{1}{4}$ sec. cor., from which A fir, 24 ins. in diam., bears S.15°E., dist. 80 lks., marked $\frac{1}{4}$ S B T; also A fir, 5 ins. in diam., bears N.20°W., dist. 29 lks., marked $\frac{1}{4}$ S B T.
78.00	Pendleton and LaGrande Road, course W.
81.06	To cor. to secs. 4, 5, 8 and 9.