

Subdivisions of T. 1 N., R. 34 E.

Chains	A pine, 14 ins. in diam., bears N.5'W., dist. 236 lks., marked $\frac{1}{4}$ S B T.
52.00	Top of ridge, course N.
80.12	To cor. to secs. 29, 30, 31 and 32. Land, mountainous. 80.12 chs. Pine timber in canyons. Good bunch grass. Soil, 2nd rate.
	West on random between secs. 30 and 31. Var. 22° E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
82.72	Intersect T. line, 76 lks. N. of cor. to secs. 25, 30, 31 and 36. Thence I run N.89°28'E. on true line.
42.72	Set basalt stone, 15x10x10 ins., 10 ins. in the ground, marked $\frac{1}{4}$ on N. face, for $\frac{1}{4}$ sec. cor. Raised a mound of stone over it.
52.72	Top of mountain.
65.72	Canyon, course S.E.
82.72	To cor. to secs. 29, 30, 31 and 32. Land, rough and mountainous. 82.72 chs. Soil, 3rd rate.
	North between secs. 29 and 30. Var. 22° E.
40.00	Set basalt stone, 11x9x7 ins., 7 ins. in the ground, marked $\frac{1}{4}$ on W. face, for $\frac{1}{4}$ sec. cor. Raised a mound of stone over it. Pits impracticable.
65.00	Gulch, course S.W.
68.00	Ascend mountain.
80.00	Set basalt stone, 14x12x10 ins., 9 ins. in the ground, marked with 2 notches on S. and 5 notches on E. edges, for cor. to secs. 19, 20, 29 and 30. Raised a mound of stone over it. Pits impracticable. Land, mountainous and rocky, 80 chs.; with some grass. Soil, 4th rate.