

Subdivisions of T. 1 N., R. 34 E.

Chains	N.89°43'W. on true line.
24.35	Gulch, course N.
40.29	Set post, 3 ft. long by 3 ins. sq., 24 ins. in ground, marked $\frac{1}{4}$ S on N. face, for $\frac{1}{4}$ sec. cor., from which A pine, 30 ins. in diam., bears N.15°E., dist. 150 lks., marked $\frac{1}{4}$ S B T; also A pine, 10 ins. in diam., bears N.6°E., dist. 25 lks. marked $\frac{1}{4}$ S B T.
62.00	Bottom canyon, course N.
80.58	To cor. to secs. 17, 18, 19 and 20. Land, undulating, covered with scattering pine timber. Some bunch grass. Soil, 2nd rate.
	West on random between secs. 18 and 19. Var. 19°E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
82.32	Intersect W. boundary of T., 190 lks. W. of cor. to secs. 13, 18, 19 and 24. Thence I run N.88°39'E. on true line.
25.30	Gulch, course W.
42.32	Set basalt stone, 12x8x8 ins., 8 ins. in the ground, marked $\frac{1}{4}$ on N. face, for $\frac{1}{4}$ sec. cor., from which A pine, 4 ins. in diam., bears S.40°E., dist. 31 lks., marked $\frac{1}{4}$ S B T; also A pine, 20 ins. in diam., bears N.23°W., dist. 22 lks., marked $\frac{1}{4}$ S B T.
67.30	Summit of ridge.
82.32	To cor. to secs. 17, 18, 19 and 20. Land, broken. Some bunch grass. Soil, 4th rate.
	North between secs. 17 and 18. Var. 19°E.
16.00	Head of canyon.