

Subdivisions of T. 1 N., R. 34 E.

Chains	West on random between secs. 7 and 18. Var. 18°45'E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
83.30	Intersect T. line, 158 lks. N. of cor. to secs. 7, 12, 13 and 18. Thence I run N.88°55'E. on true line.
43.30	Set a basalt stone, 16x10x8 ins., 11 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins. E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base alongside.
74.00	Canyon, course N.
83.30	To cor. to secs. 7, 8, 17 and 18. Land, mountainous, 40 chs., slopes to the W. Good grass. Soil, 2nd rate.
	North between secs. 7 and 8. Var. 18°45'E.
7.60	Canyon, course N.W.
10.00	Summit.
23.75	Canyon, course W.
40.00	Set a basalt stone, 14x12x12 ins., 9 ins. in the ground, marked $\frac{1}{4}$ on W. face, for $\frac{1}{4}$ sec. cor. and raised a mound of stone over it. Pits impracticable.
69.00	Road, course W.
75.00	Gulch, bears W.
80.00	Set a basalt stone, 18x14x14 ins., 14 ins. in the ground, for cor. to secs. 5, 6, 7 and 8, marked with 5 notches on S. and 5 on E. edges. Raised a mound of stone over it. Pits impracticable. Land, mountainous. 80 chs. Good timber in S.W. $\frac{1}{2}$ of the sec. Soil, 3rd rate.
	East on random between secs. 5 and 8. Var. 20°45'E.