

Subdivisions of T. 1 N., R. 34 E.

Chains	
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.20	Intersect N. and S. line, 30 lks. S. of cor. to secs. 4, 5, 8 and 9. Thence I run S.89°47'W. on true line.
40.10	Set a basalt stone, 18x16x14 ins., 14 ins. in the ground, marked $\frac{1}{4}$ on N. face, for $\frac{1}{4}$ sec. cor. Raised a mound of stone over it. Pits impracticable.
43.70	Draw, course N.W.
55.20	Wagon road, course S.
80.20	To cor. to secs. 5, 6, 7 and 8. Land, rolling and covered with bunch grass. Soil, 2nd rate.
West on random between secs. 6 and 7. Var. 20°45'E.	
40.00	Set temporary $\frac{1}{4}$ sec. cor.
83.55	Intersect W. T. boundary, 200 lks. N. of cor. to secs. 1, 6, 7 and 12. Thence I run N.88°38'E. on true line.
15.00	Head of gulch, good spring bears N.
43.55	Set a basalt stone, 14x8x8 ins., 10 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist. raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.
48.50	Summit.
72.30	Gulch, course N.W.
83.55	To cor. to secs. 5, 6, 7 and 8. Land, mountainous and rocky. 83.55 chs. Some bunch grass. Soil, 2nd rate.
North on random between secs. 5 and 6. Var. 20°45'East.	
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.25	Intersect N. T. bdy., 125 lks. W. of cor. to secs. 5, 6, 31 and 32. Thence I run