

Subdivisions and Allotments of T. 1 N., R. 34 E.

Chains	Sec. 5
	From the corner to secs. 5, 6, 7 and 8.
	I run
	N.89°47'E. on random line between secs. 5 and 8.
	Var. 20°45'East.
	Setting temporary corners at 20, 40 and 60 chains, and at
80.20	Intersect the N. and S. line at corner to secs. 4, 5, 8 and 9.
	Thence I run
	S.89°47'W. on true line between secs. 5 and 8.
	Var. 20°E.
20.05	Set stone, 14x9x7 ins., 10 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face, raised a mound of stone over it. Pits impracticable.
23.00	Gulch, course N.W.
35.00	Road, course N.
40.10	Intersect the $\frac{1}{4}$ sec. corner, which is a basalt stone, 18x16x14 ins., 14 ins. in the ground, marked $\frac{1}{4}$ on N. face, and mound of stone over it.
60.15	Set basalt stone, 14x12x10 ins., 10 ins. in the ground, for 1/16 sec. corner, marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
80.20	The corner to secs. 5, 6, 7 and 8. Land, rolling and covered with bunch grass. Soil, 2nd rate.
	From the 1/16 sec. corner, 20 chs. North of corner to secs. 5, 6, 7 and 8.
	I run
	N.89°47'E. on random line through the S. $\frac{1}{2}$ of sec. 5.
	Var. 21°E.
	Setting temporary corner at every 20, 40 and 60 chains, and at
80.00	Intersect the N. and S. line at 1/16 sec. corner, 20 chs. N. of corner to secs. 4, 5, 8 and 9.