

Subdivisions and Allotments of T. 1 N., R. 34 E.

Chains	Sec. 6
	N.0°54'E. on a true line in sec. 6.
	Var. 21°30' East.
20.00	Set basalt stone, 12x8x8 ins., 8 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face, and raised mound of stone over it. Pits impracticable.
	Land, rolling and inclined to North.
	Soil, 1st rate and rocky.
	Good grass.
	From the 1/16 sec. corner, 30 chs. N., and 20 chains W. of $\frac{3}{4}$ S corner between secs. 5 and 6.
	I run
	East on true line in sec. 6.
	Var. 20°30' East.
3.50	Pendleton and LaGrande wagon road, course N.W.
15.00	Gulch, course N.E.
20.00	To the 1/16 sec. corner, 30 chains N. of the $\frac{1}{4}$ sec. corner between secs. 5 and 6.
	Land, rolling and inclined to North.
	Soil, 1st rate and rocky.
	Good grass.
	Sec. 8
	From the 1/16 sec. corner, 20 chs. East from corner to secs. 5, 6, 7 and 8.
	I run
	South on true line in sec. 8.
	Var. 21° E.
8.00	Rocky flat, 100 lks. wide, course E. and W.
10.50	Road, course W.
20.00	Set stone, 10x8x6 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face, in flat Gulch, course W., raised a stone mound over it.
	Land, rolling with some rocky flats on summit of Mt.
	Soil, generally 1st rate.
	Good grass and sunflower.