

## Subdivisions and Allotments of T. 1 N., R. 34 E.

Chains	Sec. 8
	Var. 21° E.
20.00	Set a basalt stone, 10x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face, raised a mound of stone over it. Pits impracticable.
22.25	Road, course N.10°E.
28.50	Head of Draw, course W.
30.00	Set a basalt stone, 10x7x6 ins., 6 ins. in the ground, for 1/32 sec. corner marked 1/32 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
35.00	Summit, course S.W.
40.00	Set basalt stone, 12x10x8 ins., 8 ins. in the ground, for ¼ sec. corner marked ¼ on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it. Land, rolling. Soil, 1st rate. Grass and scattering pine timber.
	From ¼ sec. corner in the center of sec. 8.
	I run
	East on a true line in sec. 8.
	Var. 19° E.
7.00	Road, course N. and S.
10.02	Set basalt stone, 14x10x8 ins., 10 ins. in the ground, for 1/32 sec. corner marked 1/32 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it. Land, rolling. Soil, 1st rate. Scattering pine timber. Good grass.
	From the 1/16 sec. corner, 20 chains N. of ¼ sec. corner of secs. 8 and 17.