

## Subdivisions and Allotments of T. 1 N., R. 34 E.

Chains	Sec. 8
	<p>I run East on true line in sec. 8. Var. 19°E.</p>
8.50	Gulch, course S.E.
10.03	<p>Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/32 sec. corner marked 1/32 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it. Land, rolling. Scattering pine timber. Soil, 1st rate.</p>
	<p>From the 1/32 sec. corner, 10 chs. East from the corner to secs. 7, 8, 17 and 18.</p>
	<p>I run North on a true line in sec. 8. Var. 19° East.</p>
20.00	<p>Set basalt stone, 14x10x8 ins., 10 ins. in the ground, for 1/32 sec. corner marked 1/32 on W. face, and raised a mound of stone over it. Pits impracticable, from which A pine, - ins. diam., bears N.30°E., 165 lks. dist., marked 1/32 S B T. Land, rolling. Soil, 1st rate. Scattering pine timber and grass.</p>
	<p>From 1/32 sec. corner, 10 chs. E. and 20 chs. N., from the corner to secs. 7, 8, 17 and 18.</p>
	<p>I run East on random line in sec. 8. Var. 19°E.</p>
30.00	<p>Setting temporary corner at 10 chains, and at Intersect line at 1/16 sec. corner, 20 chs. N. of ¼ sec. cor. between secs. 8 and 17.</p>