

Field Notes of the Survey of the South Boundary of
T. 1, N., R. 35 E., by Timothy W. Davenport, under
his contract No. 102, dated July 20th, 1863.

Base Line Extension

Chains

South boundary of T. 1 N., R. 35 East
Thence East on South boundary of Sec. 31.
Variation 20° East.

35.00 Enter timber.

40.00 Set qr. sec. post, from which
A Pine 10 ins., wide bears S15°E 29 lks. dist.
" " 28 " " " N30°W 40 lks. "

80.00 Set post corner to Secs. 31 & 32, from which
A Pine 24 ins. bears N10°E 43 lks dist.
A White Fir 10 ins. in diam. bears N.30°W.30 lks. dist.
Surface of this mile undulating.
Soil, gravelly.
Timber, tamarack, pine & fir.
Undergrowth, service berry, willow & cherry.
Variation 24° East.
August 8th, 1863.

Thence,
East on South boundary of Sec. 32.
Variation 24° East.

40.00 Set qr. sec. post, from which
A Red Fir 12 ins., in dia. bears S5°E 74 lks. dist.
A Red Fir 16 ins., in dia. bears S70°W 65 lks.

52.10 A White Fir 16 inches in dia.

80.00 Set post corner to secs. 32 & 33, from which
A Hemlock, 18 inches in dia. bears S40°E. 29 lks.
A Red Fir 14 " " " " N20°W. 52 lks.
A Red Fir, 10 " " " " N40°E. 46 lks.
Variation 21°40' E.
Surface undulating. Timber, soil, etc., as in previous
mile.

Thence
East on South boundary of Sec. 33.
Var. 20°40' East.

12.00 Commence to descend.

40.00 Set qr. sec. post, from which

+25