

E. bdry., T. 1 N., R. 35 E.

Chains		
40.00	Set post for $\frac{1}{4}$ Sec. corner, from which A pine 30 ins. in diam. bears S65°E. 10 lks. A fir, 20 " " " " S60°W. 67 "	
50.55	Brook, 4 lks. wide, flows West.	-275
60.40	Rocky Point.	+350
75.45	Meacham creek, 15 lks. wide, flows E.	-750
80.00	Set post for corner to Secs. 25, 36, 30, 31, from which A fir 28 ins. diam. bears S65°W. 15 lks. " " 24 " " " S65°E. 20 " A Larch, 20 ins. " " N.20°E 23 lks. Land, mountainous. Soil, 2d rate. Good pine, fir and larch timber.	
	North on East boundary of Sec. 25. Var. 20° East.	
25.50	Summit of hill.	+800
40.00	Set post for $\frac{1}{4}$ Sec. corner, from which A Pine 28 ins. in diam. bears S. 85° West A Fir 30 ins. in diam. bears N. 15° E. 1.25 chs.	
80.00	Set post for corner to Secs. 24, 25, 19, 30, from which A Pine, 30 ins. in diam. bears N.40° E. 23 lks. " " 34 " " " " N.77° E. 85 lks.	
	Land, mountainous. Soil, 2nd rate. Good pine & fir timber.	
	North on East boundary of Sec. 24. Variation 21° East.	
40.00	Set post for $\frac{1}{4}$ Sec. corner, from which A Fir 20 ins. in diam. bears S70°W. 10 lks. " " 24 " " " " S50°E. 18 lks.	
80.00	Set post and made stone mound for corner to Secs. 13, 24, 18, 19. First half mile passes through timber; 2d half mile, through open country. Land, mountainous. Soil, 2d rate.	